Table 1: Sample list of decommissioning tasks and estimated costs

Tasks	Estimated Cost ($)
Remove Rack Wiring	$2,459
Remove Panels	$2,450
Dismantle Racks	$12,350
Remove Electrical Equipment	$1,850
Breakup and Remove Concrete Pads or Ballasts	$1,500
Remove Racks	$7,800
Remove Cable	$6,500
Remove Ground Screws and Power Poles	$13,850
Remove Fence	$4,950
Grading	$4,000
Seed Disturbed Areas	$250
Truck to Recycling Center	$2,250
Current Total	**$60,200**
Total After 20 Years (2.5% inflation rate)	**$98,900**